

Government of Maharashtra

SEAC 2212/CR-101 /TC-2
Environment department,
Room No. 217, 2nd floor,
Mantralaya Annexe,
Mumbai 400 032
Date: 30th November, 2012

To,
M/s. Wellwisher Homes.
At Village Hadapsar,
Tal Haveli, Dist- Pune

Subject: Environmental clearance for the proposed Residential Project S.No.202/A,202B/1/1 to 202/B / 1/7,202/b/2 to 202/B/4 of village Hadapsar, Tal Haveli, Dist. Pune by M/s. Wellwisher Homes - Environmental clearance regarding.

Sir,

This has reference to your communication on the above mentioned subject. The proposal was considered as per the EIA Notification - 2006, by the State Level Expert Appraisal Committee, Maharashtra in its 62nd meeting decided to recommend the project for prior environmental clearance to SEIAA. Information submitted by you has been considered by State Level Environment Impact Assessment Authority in its 53rd Meeting.


2. It is noted that the proposal is for grant of Environmental Clearance for proposed Residential Project S.No.202/A,202B/1/1 to 202/B / 1/7,202/b/2 to 202/B/4 of village Hadapsar, Tal Haveli, Dist. Pune. SEAC considered the project under screening category 8(b) B1 as per EIA Notification 2006.

Brief Information of the project is summarized during SEAC & SEIAA Meetings as:

Name of the Project	:	"Leisure Town"
Project Proponent	:	M/s. Wellwisher Homes.
Location of the project	:	S.No.202/A,202B/1/1 To 202/B/1/7. 202/B/2 To 202/B/4, Village Hadapsar, Tehsil Haveli, Dist.-Pune,
Type of Project	:	Residential development with convenient shopping .
Category	:	8 (b), B1
Whether in Corporation / Municipal / Other area	:	Town Planning.
Applicability of the DCR	:	Regional planning Development Control Rule

Total plot area (Sq.m) Deductions Net plot area	Plot Area: 89362.00 Sq. Mt. Deductions (18 M Wide R.P Road): 4281.72 Sq. mt. Net Plot Area: 85080.00.7Sq. mt.				
Permissible FSI (including TDR etc.)	FSI on Balance Plot-63,810.21 sq.mt 20% paid FSI Premium- 12,762.04 sq.mt 18 m wide RP Road- 4281.72 sq.mt Amenity FSI- 12762.04 sq.mt. Total FSI – 93615.97 sq.mt				
Proposed Built –UP Area (FSI & Non FSI)	<ul style="list-style-type: none"> • FSI area (sq. m.): 86869.75 sq.mt • Non FSI area (sq. m.): 91808.82 Sq. Mt • Total BUA area (sq. m.): 1,78,678.57 Sq.mt 				
Ground – coverage percentage (%) (Note : percentage of plot not open to sky)	15.6%				
Estimated cost of the project	220 Cr.				
No. of building & its configuration (s)	Development	Bldg. Type	Wings	Configuration	
	Residential	1	A	Stilt + 12	
		2	B	Stilt + 12	
		3	C, D, E, F, G, H, I, J, K.	Stilt + 12	
		4	L, M, N, O, P	Stilt + 12	
		5	Q	Stilt + 9	
		Total	17		
	Commercial		1	G	
	Amenity-1	Hospital	1	G+5	
	Amenity-2	School	1	G+5	
Number of tenants and shops		Bldg. Type	No. of Bld g.	No. of Flats/ Shops	Total No. of Flats
	Residential	(Building 1 (Stilt + 12)	A	94	94
		Building 2 (Stilt + 12)	B	94	94
		Building 3 (Stilt + 12)	C, D, E, F, G, H, I, J, K.	94	846
		Building 4 (Stilt	L,	70	140

		+ 12)	P, M, N,O	94	282
		Building 5 (Stilt + 9)	Q	9	9
		Total	17	--	1465
		Commercial	1	22 Shops	22
		Amenity-1 Hospital (G+5)	1	240 Beds	
		Amenity-2 School (G+5)	1	36 classroom	
Number of expected residents / users	Residential – 6957 no. Commercial – 87 Nos. Amenity 1 &2 - 2796 nos. Total No. - 9840 Nos.				
Tenant density per hector	181 / Hectare				
Height of the building(s)	36m				
Right of way	18 m				
Turning radius for easy access of fire tender movement from all around the building excluding the width for the plantation	6.0 m Minimum Driveways with 9.0 m radius and wider space at turning.				
Details of the demolition with disposal (If applicable)	Sr.No.	Details	Quantification		
	1	Bricks	176000		
	2	Concrete	544 m3		
	3	Steel	32 MT		
	4	Mangalore tiles	11200 sq.ft		
	5	Wooden frame	2.4 m3		
	6	Flooring	16000 sq.mt		
	7	Glass	1152 sq.ft		
Total Water Requirement	<p>Dry season:</p> <ul style="list-style-type: none"> • Fresh water (CMD): 677 & Source: Grampanchayat/ Tanker • Recycled water (CMD):522 • Total Water Requirement (CMD):1199 • Swimming pool make up (Cum): 5 • Fire fighting (Cum): 450 <p>Wet Season:</p> <ul style="list-style-type: none"> • Fresh water (CMD): 672 & Source: Grampanchayat/ Tanker • Recycled water (CMD):370 • Total Water Requirement (CMD): 1047 • Swimming pool make up (CMD): 5 • Fire fighting (CMD):450 				
Rain Water Harvesting (RWH)	<ul style="list-style-type: none"> • Level of the Ground water table: 8.1 m. • Size, no of recharge pits and Quantity: 				



	<p>Recharge pits (31 Nos.) : Size 1.5 X1.5 X1.5 mt Recharge borewells 8 Nos.: 60mt Depth</p> <ul style="list-style-type: none"> Each recharge bore well contributes 5%, so eight bore wells contribute about 40% of rainwater harvesting potential of Hadapsar Wellwisher sites. In addition to this recharge is possible through the recharge pits as well Budgetary allocation (Capital cost and O&M cost): <ul style="list-style-type: none"> Capital Cost : Rs.10.2 Lakh O & M Cost: Rs. 5.45 Lakh/ Annum
Strom water drainage	<p>Natural water drainage pattern: Contoured land sloping From east to west (from 101 to 94) Size of SWD: 300 TO 450MM WIDE drain with 1:150 slope</p>
Sewage and waste water	<ul style="list-style-type: none"> Sewage generation (CMD) : 833 [(Resi+Comm.=754)+(School=79)] STP technology: Extended aeration system Capacity of STP (CMD): 2 nos. of STP <ol style="list-style-type: none"> Residential & Commercial: 755 M³ Amenity-2 (School) : 80 M³ <p>Location of the STP:</p> <ol style="list-style-type: none"> Residential & Commercial: Near Wing B Amenity-2 (School) : Near Playground <p>Waste Water Generation:- 793 M3 Capacity for ETP :- 100 M3</p> <p>Location of the ETP : Near Playground</p> <ul style="list-style-type: none"> DG sets (during emergency): Load considered in the Common D.G. Set. Budgetary allocation For STP and ETP (Capital cost and O&M cost): <ul style="list-style-type: none"> STP - Capital cost : Rs.99.6 lakhs , STP - O &M cost : 10 Lakhs/ Annum ETP - Capital cost : Rs.30 lakhs , ETP - O &M cost : 4 Lakhs/ Annum
Solid waste Management	<p>Waste generation in the operation Phase:</p> <ul style="list-style-type: none"> Dry waste (Kg/day): 2179 Wet waste (Kg/day):2093 E – waste (Kg/month):-- Nil Hazardous waste (Kg/day): Negligible Biomedical waste (Kg/day) (If applicable):- 60 STP Sludge (Dry sludge) (Kg/day):Approx - 140 <p>Mode of Disposal of waste:</p> <p>The project proponents have proposed provision for segregation and collection of bio-degradable waste and recyclable waste within the premises. Vessel-composting of wet garbage will be done. Dry garbage will be handed over to the authorized contractors to recycle to reduce the load on dumping ground. Dried sludge from STP will be used as manure.</p>



	<p>Area requirement:</p> <ul style="list-style-type: none"> • Area required for Solid waste management: 168.5 sq.mt. <p>Budgetary allocation (Capital cost and O&M cost):</p> <ul style="list-style-type: none"> • Capital Cost : Rs. 64.63 Lakhs • O & M Cost : Rs. 9.17 Lakhs /Annum
Green Belt Development	<p>Total RG area: Playgrounds :1777 Sq.mt. Hardscape : 1345 Sq.mt</p> <p>RG area under green belt: RG on ground (sq. m.): Total : 30320</p> <ul style="list-style-type: none"> • Tree Cover : 27999 Sq.Mt. • Lawn : 1790 Sq.Mt. • Shrub Bed : 531 Sq.Mt. <p>Number, size, age and species of trees to be cut, trees to be transplanted: Existing trees: 253 nos. Retained - 47 nos. Transplant – 104 nos. Uprooted – 102 Nos.</p> <p>Budgetary allocation (Capital cost and O&M cost)</p> <ul style="list-style-type: none"> • Capital Cost : Rs.166.76 Lacs • O & M Cost : 26.68 lacs/ Annum
Energy	<p>Power supply: Connected Load – 31090 kW Maximum Demand – 9384 kVA D.G. Set – 6 nos. of DG sets of Capacity 750 kVA for each</p> <p>Energy saving by non-conventional method: Electrical & LV Systems:</p> <ul style="list-style-type: none"> • Copper conductor cables are specified for sizes of 16 sq mm and below, this will reduce losses and improve reliability. • Power factor shall be maintained 0.92 or higher. This will reduce electrical power distribution losses in the installation. • Timers shall be used to switch ON / OFF external landscape and facade lighting. • Compact Fluorescent Lamps (CFL's) with high frequency ballast shall be used for corridors areas. • Energy efficient fluorescent tube lights (T-5) shall be used for common areas & car parking • All fluorescent light fixtures are specified to incorporate electronic chokes which have less watt-loss compared to electro-magnetic chokes and result in superior operating power factor. This indirectly saves energy. Electronic chokes also improves life of the fluorescent lamps. • Energy efficient fluorescent lamps & CFL lamps which give approx. 30% more light output for the same watts consumed and therefore require less nos. of fixtures and corresponding lower point wiring costs.



	<p>Budgetary allocation (Capital cost and O&M cost)- For Electrical System</p> <ul style="list-style-type: none"> • Capital Cost : Rs. 274.409 Lakhs • O & M Cost : Rs.5.8201 Lakhs/ Annum <p>Budgetary allocation (Capital cost and O&M cost)- For Solar water Heating system Panels</p> <ul style="list-style-type: none"> • Capital Cost : Rs. 369 Lakhs • O & M Cost : Rs.11.808 Lakhs/ Annum <p>Number and capacity of the DG sets to be used: DG set- 6 nos. of DG sets having 750 KVA capacity for each Type of fuel used : HSD</p>																																																																							
Traffic Management	<ul style="list-style-type: none"> • Total Parking area: 27410.65 Sq.mt. <table border="1" data-bbox="571 775 1406 1227"> <thead> <tr> <th rowspan="2">Parking</th> <th colspan="4">Required as per DC rule</th> <th colspan="4">Provided</th> </tr> <tr> <th>4 W</th> <th>2 W</th> <th>Cycles</th> <th>Ambu / Bus</th> <th>4 W</th> <th>2 W</th> <th>Cycles</th> <th>Ambu / Bus</th> </tr> </thead> <tbody> <tr> <td>Residential</td> <td>656</td> <td>3048</td> <td>5248</td> <td>-</td> <td>656</td> <td>3048</td> <td>3070</td> <td>-</td> </tr> <tr> <td>Commercial</td> <td>10</td> <td>10</td> <td>10</td> <td>-</td> <td>121</td> <td>10</td> <td>10</td> <td>-</td> </tr> <tr> <td>Hospital</td> <td>12</td> <td>12</td> <td>12</td> <td>12</td> <td>99</td> <td>12</td> <td>12</td> <td>12</td> </tr> <tr> <td>School</td> <td>52</td> <td>52</td> <td>52</td> <td>52</td> <td>-</td> <td>52</td> <td>52</td> <td>37</td> </tr> <tr> <td>Visitor</td> <td>146</td> <td>146</td> <td>146</td> <td>-</td> <td>-</td> <td>146</td> <td>146</td> <td>-</td> </tr> <tr> <td>Total</td> <td>876</td> <td>3268</td> <td>5468</td> <td>64</td> <td>876</td> <td>3268</td> <td>3290</td> <td>49</td> </tr> </tbody> </table> <p>Width of all Internal roads (m): 6-12m. wide</p>	Parking	Required as per DC rule				Provided				4 W	2 W	Cycles	Ambu / Bus	4 W	2 W	Cycles	Ambu / Bus	Residential	656	3048	5248	-	656	3048	3070	-	Commercial	10	10	10	-	121	10	10	-	Hospital	12	12	12	12	99	12	12	12	School	52	52	52	52	-	52	52	37	Visitor	146	146	146	-	-	146	146	-	Total	876	3268	5468	64	876	3268	3290	49
Parking	Required as per DC rule				Provided																																																																			
	4 W	2 W	Cycles	Ambu / Bus	4 W	2 W	Cycles	Ambu / Bus																																																																
Residential	656	3048	5248	-	656	3048	3070	-																																																																
Commercial	10	10	10	-	121	10	10	-																																																																
Hospital	12	12	12	12	99	12	12	12																																																																
School	52	52	52	52	-	52	52	37																																																																
Visitor	146	146	146	-	-	146	146	-																																																																
Total	876	3268	5468	64	876	3268	3290	49																																																																
Environmental Management plan Budgetary Allocation	<p>Construction phase (with Break-up):</p> <ul style="list-style-type: none"> • Capital cost • O & M cost (Please ensure manpower and other details) <table border="1" data-bbox="576 1505 1369 1848"> <thead> <tr> <th>SR. NO.</th> <th>Parameter</th> <th>Total cost (Rs. in lacs)</th> </tr> </thead> <tbody> <tr> <td>1</td> <td>Water for dust suppression</td> <td>0.24</td> </tr> <tr> <td>2</td> <td>Site sanitation & safety</td> <td>0.5</td> </tr> <tr> <td>3</td> <td>Environmental monitoring</td> <td>1.92</td> </tr> <tr> <td>4</td> <td>Disinfection</td> <td>0.6</td> </tr> <tr> <td>5</td> <td>Health check up</td> <td>2.4</td> </tr> <tr> <td></td> <td>Total cost</td> <td>5.66</td> </tr> </tbody> </table> <p>Operation Phase (with Break-up)-</p> <ul style="list-style-type: none"> • Capital cost • O&M cost (Please ensure manpower and other details) <table border="1" data-bbox="576 1984 1369 2033"> <thead> <tr> <th>Sr. no.</th> <th>Parameter</th> <th>Set up cost</th> <th>Operatio</th> </tr> </thead> <tbody> <tr> <td></td> <td></td> <td></td> <td></td> </tr> </tbody> </table>	SR. NO.	Parameter	Total cost (Rs. in lacs)	1	Water for dust suppression	0.24	2	Site sanitation & safety	0.5	3	Environmental monitoring	1.92	4	Disinfection	0.6	5	Health check up	2.4		Total cost	5.66	Sr. no.	Parameter	Set up cost	Operatio																																														
SR. NO.	Parameter	Total cost (Rs. in lacs)																																																																						
1	Water for dust suppression	0.24																																																																						
2	Site sanitation & safety	0.5																																																																						
3	Environmental monitoring	1.92																																																																						
4	Disinfection	0.6																																																																						
5	Health check up	2.4																																																																						
	Total cost	5.66																																																																						
Sr. no.	Parameter	Set up cost	Operatio																																																																					



			maintain ace cost (Rs. in lacs/ann um)
1	STP cost	129.6	14
2	Rain water harvesting	0.7	5.54
3	Environmental monitoring	MoEF Approved Laboratory	7.82
4	Solar lights	369.00	11.81
5	Electrical System	274.41	13.72
6	Gardening	166.76	26.68
7	Solid waste management	64.63	9.17
TOTAL COST		1005.1	88.74

3. The proposal has been considered by SEIAA in its 53rd meeting & decided to accord environmental clearance to the said project under the provisions of Environment Impact Assessment Notification, 2006 subject to implementation of the following terms and conditions :-

- (i) This environmental clearance is issued subject to land use verification. Local authority / planning authority should ensure this with respect to Rules, Regulations, Notifications, Government Resolutions, Circulars, etc. issued if any. This environmental clearance issued with respect to the environmental consideration and it does not mean that State Level Impact Assessment Authority (SEIAA) approved the proposed land use.
- (ii) The height, Construction built up area of proposed construction shall be in accordance with the existing FSI/FAR norms of the urban local body & it should ensure the same along with survey number before approving layout plan & before according commencement certificate to proposed work. Plan approving authority should also ensure the zoning permissibility for the proposed project as per the approved development plan of the area.
- (iii) "Consent for Establishment" shall be obtained from Maharashtra Pollution Control Board under Air and Water Act and a copy shall be submitted to the Environment department before start of any construction work at the site.
- (iv) All required sanitary and hygienic measures should be in place before starting construction activities and to be maintained throughout the construction phase.
- (v) Project proponent shall ensure completion of STP, MSW disposal facility, green belt development prior to occupation of the buildings. No physical occupation or allotment will be given unless all above said environmental infrastructure is installed and made functional including water requirement in Para 2. Prior certification from appropriate authority shall be obtained.
- (vi) Provision shall be made for the housing of construction labour within the site with all necessary infrastructure and facilities such as fuel for cooking, mobile toilets, mobile STP, safe drinking water, medical health care, crèche and First Aid Room etc.
- (vii) Adequate drinking water and sanitary facilities should be provided for construction workers at the site. Provision should be made for mobile toilets. The safe disposal of



wastewater and solid wastes generated during the construction phase should be ensured.

- (viii) The solid waste generated should be properly collected and segregated. dry/inert solid waste should be disposed off to the approved sites for land filling after recovering recyclable material
- (ix) Wet garbage should be treated by Organic Waste Converter and treated waste (manure) should be utilized in the existing premises for gardening. And, no wet garbage will be disposed outside the premises. Local authority should ensure this.
- (x) Arrangement shall be made that waste water and storm water do not get mixed.
- (xi) All the topsoil excavated during construction activities should be stored for use in horticulture / landscape development within the project site.
- (xii) Additional soil for leveling of the proposed site shall be generated within the sites (to the extent possible) so that natural drainage system of the area is protected and improved.
- (xiii) Green Belt Development shall be carried out considering CPCB guidelines including selection of plant species and in consultation with the local DFO/ Agriculture Dept.
- (xiv) Disposal of muck during construction phase should not create any adverse effect on the neighboring communities and be disposed taking the necessary precautions for general safety and health aspects of people, only in approved sites with the approval of competent authority.
- (xv) Soil and ground water samples will be tested to ascertain that there is no threat to ground water quality by leaching of heavy metals and other toxic contaminants.
- (xvi) Construction spoils, including bituminous material and other hazardous materials must not be allowed to contaminate watercourses and the dumpsites for such material must be secured so that they should not leach into the ground water.
- (xvii) Any hazardous waste generated during construction phase should be disposed off as per applicable rules and norms with necessary approvals of the Maharashtra Pollution Control Board.
- (xviii) The diesel generator sets to be used during construction phase should be low sulphur diesel type and should conform to Environments (Protection) Rules prescribed for air and noise emission standards.
- (xix) The diesel required for operating DG sets shall be stored in underground tanks and if required, clearance from concern authority shall be taken.
- (xx) Vehicles hired for bringing construction material to the site should be in good condition and should have a pollution check certificate and should conform to applicable air and noise emission standards and should be operated only during non-peak hours.
- (xxi) Ambient noise levels should conform to residential standards both during day and night. Incremental pollution loads on the ambient air and noise quality should be closely monitored during construction phase. Adequate measures should be made to reduce ambient air and noise level during construction phase, so as to conform to the stipulated standards by CPCB/MPCB.
- (xxii) Fly ash should be used as building material in the construction as per the provisions of Fly Ash Notification of September 1999 and amended as on 27th August, 2003. (The above condition is applicable only if the project site is located within the 100Km of Thermal Power Stations).
- (xxiii) Ready mixed concrete must be used in building construction.
- (xxiv) The approval of competent authority shall be obtained for structural safety of the buildings due to any possible earthquake, adequacy of fire fighting equipments etc. as per National Building Code including measures from lighting.
- (xxv) Storm water control and its re-use as per CGWB and BIS standards for various applications.

8-


- (xxvi) Water demand during construction should be reduced by use of pre-mixed concrete, curing agents and other best practices referred.
- (xxvii) The ground water level and its quality should be monitored regularly in consultation with Ground Water Authority.
- (xxviii) The installation of the Sewage Treatment Plant (STP) should be certified by an independent expert and a report in this regard should be submitted to the Ministry before the project is commissioned for operation. Treated effluent emanating from STP shall be recycled/refused to the maximum extent possible. Treatment of 100% gray water by decentralized treatment should be done. Necessary measures should be made to mitigate the odour problem from STP.
- (xxix) Local body should ensure that no occupation certification is issued prior to operation of STP/MSW site etc. with due permission of MPCB.
- (xxx) Permission to draw ground water shall be obtained from the competent Authority prior to construction/operation of the project.
- (xxxi) Separation of gray and black water should be done by the use of dual plumbing line for separation of gray and black water.
- (xxxii) Fixtures for showers, toilet flushing and drinking should be of low flow either by use of aerators or pressure reducing devices or sensor based control.
- (xxxiii) Use of glass may be reduced up to 40% to reduce the electricity consumption and load on air conditioning. If necessary, use high quality double glass with special reflective coating in windows.
- (xxxiv) Roof should meet prescriptive requirement as per Energy Conservation Building Code by using appropriate thermal insulation material to fulfill requirement
- (xxxv) Energy conservation measures like installation of CFLs /TFLs for the lighting the areas outside the building should be integral part of the project design and should be in place before project commissioning. Use CFLs and TFLs should be properly collected and disposed off/sent for recycling as per the prevailing guidelines/rules of the regulatory authority to avoid mercury contamination. Use of solar panels may be done to the extent possible like installing solar street lights, common solar water heaters system. Project proponent should install, after checking feasibility, solar plus hybrid non conventional energy source as source of energy.
- (xxxvi) Diesel power generating sets proposed as source of back up power for elevators and common area illumination during operation phase should be of enclosed type and conform to rules made under the Environment (Protection) Act, 1986. The height of stack of DG sets should be equal to the height needed for the combined capacity of all proposed DG sets. Use low sulphur diesel. The location of the DG sets may be decided with in consultation with Maharashtra Pollution Control Board.
- (xxxvii) Noise should be controlled to ensure that it does not exceed the prescribed standards. During nighttime the noise levels measured at the boundary of the building shall be restricted to the permissible levels to comply with the prevalent regulations.
- (xxxviii) Traffic congestion near the entry and exit points from the roads adjoining the proposed project site must be avoided. Parking should be fully internalized and no public space should be utilized.
- (xxxix) Opaque wall should meet prescriptive requirement as per Energy Conservation Building Code, which is proposed to be mandatory for all air-conditioned spaces while it is aspirational for non-air-conditioned spaces by use of appropriate thermal insulation material to fulfill requirement
- (xl) The building should have adequate distance between them to allow movement of fresh air and passage of natural light, air and ventilation
- (xli) Regular supervision of the above and other measures for monitoring should be in place all through the construction phase, so as to avoid disturbance to the surroundings.



- (xlii) Under the provisions of Environment (Protection) Act, 1986, legal action shall be initiated against the project proponent if it was found that construction of the project has been started without obtaining environmental clearance.
 - (xliii) Six monthly monitoring reports should be submitted to the Department and MPCB.
 - (xliv) A complete set of all the documents submitted to Department should be forwarded to the MPCB
 - (xlv) In the case of any change(s) in the scope of the project, the project would require a fresh appraisal by this Department.
 - (xlvi) A separate environment management cell with qualified staff shall be set up for implementation of the stipulated environmental safeguards.
 - (xlvii) Separate funds shall be allocated for implementation of environmental protection measures/EMP along with item-wise breaks-up. These cost shall be included as part of the project cost. The funds earmarked for the environment protection measures shall not be diverted for other purposes and year-wise expenditure should reported to the MPCB & this department.
 - (xlviii) The project management shall advertise at least in two local newspapers widely circulated in the region around the project, one of which shall be in the Marathi language of the local concerned within seven days of issue of this letter, informing that the project has been accorded environmental clearance and copies of clearance letter are available with the Maharashtra Pollution Control Board and may also be seen at Website at <http://ec.maharashtra.gov.in>.
 - (xlix) Project management should submit half yearly compliance reports in respect of the stipulated prior environment clearance terms and conditions in hard & soft copies to the MPCB & this department, on 1st June & 1st December of each calendar year.
- (I) A copy of the clearance letter shall be sent by proponent to the concerned Municipal Corporation and the local NGO, if any, from whom suggestions/representations, if any, were received while processing the proposal. The clearance letter shall also be put on the website of the Company by the proponent.
 - (li) The proponent shall upload the status of compliance of the stipulated EC conditions, including results of monitored data on their website and shall update the same periodically. It shall simultaneously be sent to the Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB. The criteria pollutant levels namely; SPM, RSPM, SO₂, NO_x (ambient levels as well as stack emissions) or critical sector parameters, indicated for the project shall be monitored and displayed at a convenient location near the main gate of the company in the public domain.
 - (lii) The project proponent shall also submit six monthly reports on the status of compliance of the stipulated EC conditions including results of monitored data (both in hard copies as well as by e-mail) to the respective Regional Office of MoEF, the respective Zonal Office of CPCB and the SPCB.
 - (liii) The environmental statement for each financial year ending 31st March in Form-V as is mandated to be submitted by the project proponent to the concerned State Pollution Control Board as prescribed under the Environment (Protection) Rules, 1986, as amended subsequently, shall also be put on the website of the company along with the status of compliance of EC conditions and shall also be sent to the respective Regional Offices of MoEF by e-mail.
4. The environmental clearance is being issued without prejudice to the action initiated under EP Act or any court case pending in the court of law and it does not mean that project



proponent has not violated any environmental laws in the past and whatever decision under EP Act or of the Hon'ble court will be binding on the project proponent. Hence this clearance does not give immunity to the project proponent in the case filed against him, if any or action initiated under EP Act.

5. In case of submission of false document and non compliance of stipulated conditions, Authority/ Environment Department will revoke or suspend the Environmental Clearance without any intimation and initiate appropriate legal action under Environmental Protection Act, 1986.
6. The Environment department reserves the right to add any stringent condition or to revoke the clearance if conditions stipulated are not implemented to the satisfaction of the department or for that matter, for any other administrative reason.
7. **Validity of Environment Clearance:** The environmental clearance accorded shall be valid for a period of 5 years.
8. In case of any deviation or alteration in the project proposed from those submitted to this department for clearance, a fresh reference should be made to the department to assess the adequacy of the condition(s) imposed and to incorporate additional environmental protection measures required, if any.
9. The above stipulations would be enforced among others under the Water (Prevention and Control of Pollution) Act, 1974, the Air (Prevention and Control of Pollution) Act, 1981, the Environment (Protection) Act, 1986 and rules there under, Hazardous Wastes (Management and Handling) Rules, 1989 and its amendments, the public Liability Insurance Act, 1991 and its amendments.
10. Any appeal against this environmental clearance shall lie with the National Green Tribunal , Van Vigyan Bhawan, Sec- 5, R.K. Puram, New Dehli – 110 022, if preferred, within 30 days as prescribed under Section 16 of the National Green Tribunal Act, 2010.



(Valsa R Nair Singh)
Secretary, Environment
department & MS, SEIAA

Copy to:

1. Shri. P.M.A Hakeem, IAS (Retd.), Chairman, SEIAA, 'Jugnu' Kottaram Road, Calicut- 673 006 Kerla.
2. Dr. S. Devotta, Chairman, SEAC, T2/302 Sky City, Vanagaram –Ambattur Road, Chennai – 600 095
3. Additional Secretary, MOEF, 'Paryavaran Bhawan' CGO Complex, Lodhi Road, New Delhi – 110510
4. Member Secretary, Maharashtra Pollution Control Board, with request to display a copy of the clearance.

5. The CCF, Regional Office, Ministry of Environment and Forest (Regional Office, Western Region, Kendriya Paryavaran Bhavan, Link Road No- 3, E-5, Ravi-Shankar Nagar, Bhopal- 462 016). (MP).
6. Regional Office, MPCB, Pune.
7. Collector, Pune.
8. Commissioner, Pune Municipal Corporation, Pune.
9. IA- Division, Monitoring Cell, MoEF, Paryavaran Bhavan, CGO Complex, Lodhi Road, New Delhi-110003.
10. Director (TC-1), Dy. Secretary (TC-2), Scientist-1, Environment Department.
11. Select file (TC-3).